

INDIA PAVILION, MOSCOW BOOK FAIR 2025 HALL NO. 57, NATIONAL BOOK TRUST, INDIA

Client: National Book Trust, Govt of India

Designers: National Institute of Design, Ahmedabad, India

BoQ for Fabrication & Installation of the INDIA PAVILION at Moscow International Book Fair at Moscow, Russia (Area 350 sq mt)

No.	Scope of work	Unit	Quantity	Unit Price	Amount
A	Exhibitor Stalls and other structures				
A.1	30mm Partition 18MM PLY + 12MM MDF				
	<p>Providing, making, fixing and positioning 30mm thick partition wall unit with ply (18mm) + 12mm MDF support the book shelves as per the reference drawing.</p> <p>Interconnected as per reference drawing. Finished with laquer polish / other suitable finish as discussed with the designer.</p> <p>Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site.</p> <p>Mode of measurement: As per the drawing provided & on site measurement.. <i>Minor changes in dimensions can be accommodated after a mandatory discussion and approval from the designer; whenever arising from the system limitation or modularity.</i></p>				
A.1.1	FF2: one Module - 2685mm x 1196 x 3100mm high	Combination	20		
A.2	50 MM Thick Partition (10 MM MDF + 25 MM ply + 15mm MDF) with colour as per selection				
	<p>Providing, making, fixing and positioning partition wall unit with ply (25mm) + 10mm & 15mm MDF as per the reference drawing. Interconnected as per reference drawing. Finished with paint & Graphics finish as discussed with the designer.</p> <p>Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site.</p> <p>Mode of measurement: As per the drawing provided & on site measurement.. <i>Minor changes in dimensions can be accommodated after a mandatory discussion and approval from the designer; whenever arising from the system limitation or modularity.</i></p>				
A.2.1	EXTERNAL WALL	Sqmt	286.43		
A.3	VIDEO LED HANGING SUPPORT UNIT				
	<p>Providing, making, fixing video led hanging supporting unit made of Metal structure with MDF cadding on top as per reference drawing / images.</p> <p>The unit shall be supported with the true ceiling to be as per norms and feasibility with required metal fabrication work.</p> <ul style="list-style-type: none"> - Load Capacity: Must support LED wall weight (Considering the safety factor) - Mounting: Fixed to true ceiling (concrete/slab) via expansion anchors - Suspension: Steel cables/channels (As per requirement) <p>Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site.</p> <p>Mode of measurement: As per the drawing provided & on site measurement.</p>				
A.3.1	DIA 11354 mm X 1100 mm OUT to OUT DIMENSION	combination	1		
A.4	INFORMATION DESK				
	<p>Custom Table made as per drawing specifications in pine wood / rubber wood / Ply with walnut Lacquer finish as per the reference drawing. All hinges and metal members shall be in brass finish - members D3 & D4</p> <p>Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site.</p> <p>Mode of measurement: As per the drawing provided & on site measurement.</p>				
A.4.1	FF8 Unit size 1252 x 652 x 925 mm	Nos.	2		

A.5	BOOK RACK Providing, making, fixing and positioning book display / Book rack unit shall be laminated finish MDF having multiple space for the book storage as per the reference drawing.Provision for lighting under each shelf -Extrenal Frame work shall be made of 18MM Thick MDF all around Laminate on both faces colour - Off White PVC edge in White -The internal Shelves shall be 18MM Thick MDF adjustable shelf Laminate on both faces colour - Off White PVC edge in White -The back shall be 12MM Thick MDF Back Laminate on both faces & 6mm internal stopper in laminate finish -The top and bottom facia shall be of 12MM Thick MDF with laminate finish in colour- Off White PVC edge in white Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.5.1	BOOK RACK 01-FF1 (750 X 2895 MM)	Nos.	100		
A.5.2	INDIA RUSSIA EXCHANGE 6140 x 2950 MM HT	combination	1		
A.5.3	COLLECTIVE EXHIBIT 10352 X 2950 MM HT	combination	1		
A.5.4	BOOK RACK 02 - FF10 (750 X 2895 MM)	Nos.	21		
A.6	SEATING UNIT Providing, making, fixing and positioning seating unit made of ply and laminate finish as per the reference drawing.For detail refer the Elevation / section & plan -The Internal Frame work shall be made of 18MM Thick Ply / MDF -The seating & Back shall be Laminate finish with PVC edge banding Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.6.1	SEATING FF3	Nos.	20		
A.7	INDIAN PILLAR Providing, making, fixing and positioning indian Pillar unit made of MDF as per the reference drawing. Finished with paint finish as discussed with the designer. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.7.1	INDIAN PILLAR FF6 SIZE 897 X 3015 MM	Nos.	4		
A.8	CORNICE UNIT Providing, making, fixing and positioning Cornice unit made of Styrofoam / MDF as per the reference drawing. Finished with paint finish as discussed with the designer. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.8.1	Running length of Outer Circle= 5738MM	Nos.	12		
A.8.2	Running length of Inner Circle= 4706MM	Nos.	20		
A.9	INDIAN DOLL Providing, making, fixing and positioning indian Doll made of 50MM Thick Fiber glass Painted as per selected colour as per the reference drawing. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.9.1	INDIAN DOLL - FF5 (1299 dia x 2400 mm HT)	Nos.	1		

A.10	INTERPRETER'S BOOTH Providing, making, fixing and positioning interpreter's booth made of 50MM Thick Fiber glass Painted as per selected colour as per the reference drawing with openable door & laminated table top and multiple cut out for ventilation - 50MM Thick Fiber glass openable door (including all hardware like Hinges and lock) with hand painted graphic on outer side - Lockable handle for door to be provided on both side - 20MM Thick MDF with both side laminated tabletop Colour as per selection. Provision for lighting to be given. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.10.1	INTERPRETER'S BOOTH - FF 4 (1300 dia x 2400 mm HT)	Nos.	1		
A.11	MIRROR WALLS Providing, making, fixing and positioning 4mm thick Mirror cladded on 30mm thick Partition as per the reference drawing. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.11.1	MIRROR WALLS -FF7 : M1 800 X 3015 MM	Nos.	8		
A.11.2	MIRROR WALLS -FF7 : M2 860 X 3015 MM	Nos.	7		
A.11.3	MIRROR WALLS -FF7 : M3 840 X 3015 MM	Nos.	4		
A.12	REEL UNIT Providing, making, fixing and positioning Reel unit made of 18mm thick MDF and laminate finish on both side with PVC matching edge banding & multiple back lit screen circular disks as per the reference drawing. Provision for lighting to be given. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.				
A.12.1	REEL - FF9 (2558 x 2558 mm ht)	Nos.	1		
A.13	Stretch False ceiling: Supply and install high-quality stretchable false ceiling complete with all materials, labor, and accessories as per approved design and specifications. Materials: Membrane: Premium PVC (0.18-0.3mm) or polyester fabric Finish: Matte/Gloss (RAL color matched) Track: Aluminum/PVC, powder-coated Hardware: Stainless steel (Grade 304) Provision for lighting to be given. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.	Sqmt	9		
A.14	Sheer Curtains: Supply & install sheer curtains on sliding channel system. complete with all materials, labor, and accessories as per approved design and specifications. Approved fabric/track samples. Material: Polyester/fiberglass sheer (80–120 gsm). Opacity: Semi-transparent (5–15% blackout). Finish: Double-hemmed edges (2.5 cm). Flame Retardant: Class 1 (if specified). Track: Anodized aluminum, Smooth gliding operation. Instruction: The work shall be done as per the reference drawing and as directed by the Designer. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, consumable hardwares & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill designer's design intent. The unit shall be manufactured in parts and these parts shall be assembled at site. Mode of measurement: As per the drawing provided & on site measurement.	Sqmt	36		
B	Flooring				

B.1	Medium quality carpet , to be applied directly on the exhibition hall floor and office space, as per colour scheme provided, or available. Total Floor Area: 350 sq. m.				
B.1.1	Carpet -1	Sqmt	89.5		
B.1.2	Carpet -2	Sqmt	171		
B.1.3	Carpet -3	Sqmt	32.5		
B.1.4	Carpet -4	Sqmt	57.9		
B.2	Raised Flooring / Stage platform: 150 mm raised, modular platform system of ply on top of metal /timber sturdy frame structure, covered with wooden laminate flooring as per selection and colour scheme provided. Plan area of 317 sqmt approx; exact area as per site dimensions and drawings provided	Sqmt	317		
C	Rented Furniture				
C.1	Simple chairs in metal/timber without handle; Rented furniture, selected from designs available	Nos.	21		
C.2	Stage Chairs with arm rest and cushion; Rented furniture, selected from designs available	Nos.	4		
C.3	Pantry Chair in metal/timber without handle; Rented furniture, selected from designs available	Nos.	14		
C.4	Simple chairs in modular chair with handle; Rented furniture, selected from designs available	Nos.	7		
C.5	Bar counter for Pantry Rented furniture, selected from designs available	No.	1		
C.6	Backlit bench Rented furniture, selected from designs available	Nos.	2		
C.7	Timber / Laminate top table in approximate size of as per below ; Either rented, selected from designs available.				
C.7.1	Approximate Size 1800 x 700 mm	No.	1		
C.7.2	Approximate Size 2850 x 500 mm	No.	1		
C.8	Circular Table with 600/1000mm dia glass/timber top and metallic/timber frame - rented furniture, selected from designs available.	Nos.	24		
C.9	Office Unit Walls Partition Office Unit walls made of 12mm thick MDF/plywood walls with internal timber framework with both side to be in acrylic paint as per the color scheme or as per selection. Office dimensions of Height of 2800 mm height and thickness of 50mm width, as per reference drawing	Sqmt	134.4		
C.10	Internal Door : 800 x 2100 MM HT for office space as per reference images with all hardware like door closer ,lock handles and hinges.	Nos.	6		
C.11	Two Seater Sofa Rented furniture, selected from designs available	Nos.	5		
C.12	Single Seater Sofa Rented furniture, selected from designs available	Nos.	3		
C.13	Side Table Rented furniture, selected from designs available	Nos.	5		
C.14	Storage Cabinet; approx. 1900x350x450h. Locking facilities essential.	Nos.	12		
C.15	Waste-paper bins (small size, approx. 10L)	Nos.	10		
C.16	Wet Waste bin for Pantry (medium size, approx. 15-20L)	No.	1		
C.17	Center Table: coffee Table unit 600 x 600 mm Rented furniture, selected from designs available	Nos.	2		
D	Electricals, Lighting and Audio-Visual Equipment Rentals				
D.1	Ceiling mount light of 18 / 24 watt or silimar light as per approved design	Nos.	28		
D.2	5Amp - 3 - Plug Point Power Outlet with switch, as indicated (Universal Adaptor)	Nos.	50		
D.3	164cm (65 inches) Smart TV on floor stand/mount (independant stand) with relevant connectivity accesories like HDMI cables, etc.	No.	1		
D.4	4k LED Profile light on shelves, adjusted to unit's size	Nos.	121		
	For Common Display Unit				
D.5	Spot Lights for Wall graphics on Stage, Outside Office wall, Special Display, etc	Nos.	100		
D.6	Special Spots for stage	Sets	4		
D.7	4k LED Adjustable spot lights on top of frame (10W each) - 4 light sets for each frame	Sets	10		
D.8	General lights for ambient lighting as required	Set	1		
D.9	Provision for 5 Amp Power point sockets within the office as required (at least 4 locations)	Sets	4		
D.10	DB Board and Electrical Wire cabling with safety requirements and proper arrangement as per electrical norms, as required	lumpsum			
D.11	Lapel microphone	Sets	4		
D.12	Wireless microphone	Sets	4		
D.13	Audio mixing equipment and cabling as necessary	Set	1		
D.14	Provision for 5 Amp + 15 Amp Power point sockets within the stage as required (at least 2 locations)	Sets	2		
D.15	Audio Speaker set up for Stage	Set	1		
D.16	Laptop for feed for LCD Screen	Nos.	3		
D.17	Provision for 5 Amp + 15 Amp Power point sockets In Lounge area and near pantry unit as required (at least 4 locations)	Nos.	4		
D.18	LCD Screen - 50 inch flush to the paritition (to installed on AV room Partition)	No.	1		
D.19	Large LED Video Wall Rental Use Rgb 3.91mm or as per approved panel Outdoor LED Screen or as per approved panel for Rental curved wall 13 mtr x 3 mtr ht	No.	1		
D.20	Large LED Video Wall Rental Use Rgb 3.91mm or as per approved panel Outdoor LED Screen for Rental curved wall 11 mtr diameter and 1 mtr ht.	No.	1		
D.21	Large LED Video Wall Rental Use Rgb 3.91mm or as per approved panel Outdoor LED Screen for Rental curved wall 2400 mm x 2400 mm ht.	No.	1		
E	Graphic Printing				
E.1	Digital print on Vinyl/fabric, clad on structure , of area - about 165 sq mt	Sqmt	165		
E.2	Digital print on 5MM Foam sheet + Vinyl, clad on structure	Sqmt	24.84		
F	Other Charges				
F.1	Rigging setup charges to external agency, as required.	lumpsum	1		
F.2	Electrical power charges to external agency as required.	lumpsum	1		

F.3	F & B management for 5 days of the fair including Tea - Coffee machine and Water Dispenser with ingredients and appropriate disposable cutlery/glasses/mugs.	lumpsum	1		
F.4	Daily stall cleaning & maintenance during fair period to external agency	lumpsum	1		
F.5	Assembling & dismantling charges	lumpsum	1		
F.6	Packaging & Transportation Expenses	lumpsum	1		
F.7	Project management expenses	lumpsum	1		
F.8	Appropriate hardware and other requirements for concealed electrification and structural+display system (as per availability)	lumpsum	1		
F.9	Structural Approval charges, as required	lumpsum	1		
F.10	Fire Proofing Requirements, as per norms	lumpsum	1		
F.11	Coordination with Venue Authorities regarding any and all approvals and coordination as required.	lumpsum	1		
F.12	Manpower - AV System + Experience centre + Translator + F & B + Services	lumpsum	1		
Total Amount (inclusive of all taxes)					